Republic of the Philippines
Province of South Cotabato
City of Koronadal
CITY MAYORS OFFICE - BARANGAY DEVELOPMENT PROGRAM

Project Title: **CONSTRUCTION OF MULTI-PURPOSE DRYING PAVEMENT**
Location: **PUROK SARANAY, BARANGAY NAMNAMA, CITY OF KORONADAL**
Project Cost: **₱1,455,292.62**
Duration: **100.00 Working Days**

PROGRAM OF WORKS

ITEM	SCOPE OF WORKS				
I	**SURVEY AND LAYOUT**	QUANTITY =	**1.00**	**LS.**	

Labor

	NO. OF PERSONS	NO. OF DAYS	RATE PER DAY	AMOUNT
Construction Foreman	1.00	2.00	718.00	1,436.00
Skilled Worker (Mason)	2.00	2.00	490.72	1,962.88
Laborer	6.00	2.00	442.50	5,310.00
			SUB TOTAL =	8,708.88
			DIRECT COST	8,708.88
			UNIT COST =	8,708.88

II	**EXCAVATION & EMBANKMENT**	QUANTITY =	**6.00**	**cu.m.**	

Labor

	NO. OF PERSONS	NO. OF DAYS	RATE PER	AMOUNT
Construction Foreman	1.00	20.00	718.00	14,360.00
Skilled Worker (Mason)	2.00	20.00	490.72	19,628.80
Laborer	6.00	20.00	442.50	53,100.00
			SUB TOTAL =	87,088.80

Materials

	QUANTITY	UNITS	UNIT COST	AMOUNT
Backfill	6.00	cu.m.	520.00	3,120.00
			SUB TOTAL =	3,120.00
			DIRECT COST	90,208.80
			UNIT COST =	15,034.80

III	**FORMWORKS**	QUANTITY =	**1.00**	**ls**	

Labor

	NO. OF PERSONS	NO. OF DAYS	RATE PER DAY	AMOUNT
Construction Foreman	1.00	10.00	718.00	7,180.00
Skilled Worker	2.00	10.00	528.80	10,576.00
Laborer	6.00	10.00	442.50	26,550.00
			SUB TOTAL =	44,306.00

Materials

	QUANTITY	UNITS	UNIT COST	AMOUNT
Marine Plywood 10mmx4'x8'	110.00	sheets	920.00	101,200.00
Coco Lumber 2"x2"x12'	320.00	bd.ft.	32.00	10,240.00
Coco Lumber 2"x3"x12'	170.00	bd.ft.	32.00	5,440.00
CWN #1.5	5.00	kgs	104.00	520.00
CWN #3	6.00	kgs	104.00	624.00
CWN #4	10.00	kgs	104.00	1,040.00
Nylon String 0.40mmx37m	10.00	rolls	40.00	400.00
Level Hose (Yellow)	50.00	ln.m.	25.00	1,250.00
			SUB TOTAL =	120,714.00
			DIRECT COST	165,020.00
			UNIT COST =	165,020.00

IV	**CONCRETE WORKS**	QUANTITY =	**450.00**	**sq.m.**	

Labor

	NO. OF PERSONS	NO. OF DAYS	RATE PER DAY	AMOUNT
Construction Foreman	1.00	25.00	718.00	17,950.00
Skilled Worker (Mason)	2.00	25.00	528.80	26,440.00
Laborer	6.00	25.00	442.50	66,375.00
			SUB TOTAL =	110,765.00

Materials

	QUANTITY	UNITS	UNIT COST	AMOUNT
Premium Portland Cement ASTM C595	500.00	bags	310.00	155,000.00
W. Sand	40.00	cu.m.	600.00	24,000.00
Gravel, 3/4	30.00	cu.m.	1,750.00	52,500.00
CHB 4"x8"x12"	5500.00	pcs	12.00	66,000.00
Hardware Cloth, 1/8"	1.00	ln.m.	174.94	174.94
			SUB TOTAL =	297,674.94
			DIRECT COST	408,439.94
			UNIT COST =	907.64

V **STEEL WORKS** QUANTITY = **1,390.00** **LEGTHS**

Labor

	NO. OF PERSONS	NO. OF DAYS	RATE PER	AMOUNT
Construction Foreman	1.00	10.00	718.00	7,180.00
Skilled Worker (Mason)	2.00	10.00	528.80	10,576.00
Laborer	6.00	10.00	442.50	26,550.00
			SUB TOTAL =	44,306.00

Materials

	QUANTITY	UNITS	UNIT COST	AMOUNT
Def. Bar 10mm x 6m, Grade 40	1010.00	lengths	250.00	252,500.00
Def. Bar 12mm x 6m, Grade 40	160.00	lengths	325.00	52,000.00
Def. Bar 16mm x 6m, Grade 40	220.00	lengths	640.00	140,800.00
Tie Wire #16	40.00	kgs	120.00	4,800.00
			SUB TOTAL =	450,100.00
			DIRECT COST	494,406.00
			UNIT COST =	355.69

VI **PAINTING WORKS** QUANTITY = **750.00** **SQM**

Labor

	NO. OF PERSONS	NO. OF DAYS	RATE PER	AMOUNT
Construction Foreman	1.00	32.00	718.00	22,976.00
Skilled Worker (Mason)	2.00	32.00	528.80	33,843.20
Laborer	6.00	32.00	442.50	84,960.00
			SUB TOTAL =	141,779.20

Materials

	QUANTITY	UNITS	UNIT COST	AMOUNT
MASONRY PRIMER	130.00	lengths	280.00	36,400.00
EXTERIOR PAINT	260.00	lengths	400.00	104,000.00
Rollers and Tray	12.00	sets	280.00	3,360.00
			SUB TOTAL =	143,760.00
			DIRECT COST	285,539.20
			UNIT COST =	380.72

VII **BILLBOARD** QUANTITY = **1.00** **unit**

Labor

	NO. OF PERSONS	NO. OF DAYS	RATE PER DAY	AMOUNT
Skilled Worker (Carpenter)	1.00	1.00	528.80	528.80
Laborer	1.00	1.00	441.00	441.00
			SUB TOTAL =	969.80

Materials

	QUANTITY	UNITS	UNIT COST	AMOUNT
Tarpaulin with wood Frame (8'x8')	1.00	lots	2,000.00	2,000.00
			SUB TOTAL =	2,000.00
			DIRECT COST	2,969.80
			UNIT COST =	2,969.80

TOTAL MATERIAL COST =	**₱1,017,368.94**
TOTAL LABOR COST =	**₱437,923.68**
TOTAL PROJECT COST =	**₱1,455,292.62**

PREPARED BY:

ENGR. SEVERINO JOHNROME USERO
ENGINEER-I

CHECKED BY:

ENGR. JAYSON CANTOR
ENGINEER - I

REVIEWED BY:

ENGR. JOHN JOVI Z. ANGOR
BDP COORDINATOR

RECOMMENDING APPROVAL:

ENGR. RUEL C. TIANCHON, MPA, REA, REB
CITY ENGINEER

APPROVED BY:

ATTY. ELIORDO U. OGENA
CITY MAYOR